Mold Busters - Estimate MO994

Rebuilt from FreshBooks data for this dataset. Client name and email removed; wording of the items is unchanged.

Estimate number	MO994
Created	2026-09-08
Status in FreshBooks	invoiced
Client	[removed]
Property	31 Ross St E, Smiths Falls, Ontario, K7A 4V7
Total	$3051.00 CAD (taxes included)

Notes

Estimated Project Time: 6-8 hours

Items

Item	Amount	Tax
Solution Center Agent: Natasa	$0.00	-
Inspector: Luka	$0.00	-
Attic Mold Removal Project	$2,700.00	HST 13%: $351.00
Mold Clearance Guarantee with Certificate	$0.00	-

Inspector: Luka

The inspector who prepared this estimate is:
Luka Markovic, MSC ME, CMI

Got questions? Contact Luka by phone at: 343-600-3453, or by email: luka@bustmold.com

Attic Mold Removal Project

-- Containment of the attic entrance area using polyethylene sheets, negative pressure (or an equivalent method, If permitted by actual conditions at the property) in order to help prevent any cross contamination from occurring during the removal process.

- All personal belongings should be relocated away from the attic hatch by the owner prior to the remediation process. This should be done in order for the Mold Busters remediation team to be able to bring in the necessary equipment.

-- Removal of mold from the attic area (sheathing, trusses, etc.) by means of manual wirebrushing, or other topical and abrasive removal techniques. This process is conducted alongside HEPA vacuuming, provided that conditions such as the size of the attic hatch or attic height allow for it. Additionally, we apply concentrated hydrogen peroxide or other approved fungal stain-removing agents to heavily contaminated building materials within the attic space.
Residual non-fungal staining may be present upon completion.

Portions of affected or compromised insulation may be removed and disposed of, on an as-needed basis. Any remaining insulation will be thoroughly disinfected using a fungicide.

Mold Busters' trained mold removal professionals are recommend to wear the appropriate PPE, and to complete the tasks in accordance to mold removal guidelines - https://iaq.is/mold-removal-guidelines

Price includes equipment, materials and labor fees.

Any additional items and areas that require mold removal are subject to revision and discussion with the client.

-- Disinfection

Thorough HEPA vacuuming is conducted throughout all surfaces in the affected attic area in order to remove spores, particulates, dust, and additional debris, if conditions such as the size of the attic hatch or attic height permit.

Thorough disinfection on all surfaces, including insulation, will be performed by means of concentrated fogging with a fungicide.

All remaining materials and atmosphere in the attic area will be oxidized in order to remove any residual spores, bacteria, and additional particles. An air scrubber will be deployed in the contained attic entrance area to assist in removing residual odors from products utilized during the treatment process. Residual odors may remain for up to 48-hours, depending on the quality of ventilation within the treated space.

-- Clearance

Post-remediation verification is conducted to ensure that the environment is suitable for re-occupancy.

The final clearance inspection includes a visual inspection, and surface swab testing of the affected area.

This will be performed by the Project Supervisor upon completion of the remediation process.

Mold Clearance Guarantee with Certificate

A written report following the remediation process, describing the outcome of the remediation work, any potential source issues, clearance grades, etc.

Additional recommendations will be made in this report to assist in preventing future fungal contamination.

Subtotal	$2,700.00
Taxes	$351.00
Total	$3,051.00 CAD

Terms (as shown to the client)

Why clients choose Mold Busters:

• Strong reputation with top-rated client reviews
• Competitive and transparent pricing
• Work completed according to detailed scope — no shortcuts
• If anything is not completed as outlined, we will return and address it at no additional cost

Please note that the project time is only an estimated timeframe provided for your reference. We do not charge by the hour—our pricing is all-inclusive, covering time, travel, labour, materials, and disposal for the full scope of work.

By accepting this estimate, you agree to our Terms & Conditions:
https://iaq.is/terms-conditions

Estimate pricing includes all time, travel, labor, disposal, and/or materials costs.
Unless otherwise indicated, vacancy is required for the duration of the active project hours, and reconstruction services are not provided.

A 40% booking deposit is required upon acceptance of the estimate to reserve your requested date(s) and proceed with scheduling.

Due to mold being a living organism, mold removal estimates are only valid for 60 days from the date of inspection. Acceptance of a mold removal estimate after 60 days may be subject to a re-assessment prior to proceeding.
This does not apply to asbestos or inorganic-related estimates.

Cancellation & Refund Terms:
- Cancel within 20 to 11 days before the start date: No fee.
- Cancel 10 to 3 days prior: 10% of invoice retained.
- Cancel within 48 hrs of start date: 40% of invoice retained.

Administrative fees apply.

GST/HST: 812780229RT0001
QST: 1221549895TQ0001
RBQ# 5726-4947-01