Mold Busters - Estimate MO971

Rebuilt from FreshBooks data for this dataset. Client name and email removed; wording of the items is unchanged.

Estimate number	MO971
Created	2026-09-04
Status in FreshBooks	viewed
Client	[removed]
Property	109 Stoney Pond Ct, Stittsville, ON, K2S 2E6
Total	$1689.35 CAD (taxes included)

Notes

Estimated Project Time: 4 Hours

- Keep humidity between 30-50% at all times
- Make sure that the ceiling fan is adequate, functional and clean
- Consider installing a dehumidifier

Items

Item	Amount	Tax
Solution Center Agent: Bruce	$0.00	-
Virtual Inspector: Luka	$0.00	-
Mold Removal Project	$1,495.00	HST 13%: $194.35

Virtual Inspector: Luka

The inspector who prepared this estimate is:
Luka Markovic, MSC ME, CMI

Got questions? Contact Luka by phone at: 343-600-3453, or by email: luka@bustmold.com

Mold Removal Project

--1 - Containment of Contaminated Area(s)
Containment of the bathroom with polyethylene drop sheets and zipper door(s), using negative air pressure (if permitted by actual conditions at the property), or an equivalent method, in order to prevent the cross-contamination of mold spores, dust/debris, and other particulates to other areas of the property.

Additionally, any personal belongings or large items that cannot be relocated within the affected area will be individually wrapped to protect them against dust and debris during the remediation process.

--2 - Removal of Affected Components
Removal & disposal of compromised, contaminated and/or moldy materials from the bathroom, as assessed during the initial inspection, in accordance with mold removal guidelines - https://iaq.is/mold-removal-guidelines

- Location: Bathroom -

Materials which will be removed and disposed of include:
• silicone sealant
• any other organic-based materials on an as-needed basis.

Any affected structural or framing components will be topically, manually and/or abrasively treated prior to the disinfection process.

-Topical Treatment Process:
Removal of mold from the areas by means of manual wirebrushing, or other topical and abrasive removal techniques. This is done in conjunction with HEPA vacuuming, and the application of an advanced, two-stage mold remediation protocol, initiating with high-precision stain removal techniques to revitalize the aesthetics of affected surfaces. This is seamlessly followed by the strategic application of our proprietary fungicides, meticulously designed to eliminate mold spores, thereby ensuring your space is restored to its pristine condition and safeguarded against future contamination.

The areas & materials that require treatment are:
Bathroom:
- tiles
- grout
- drywall ceiling
- other general surface areas as required

Residual non-fungal staining may be present upon completion.

All removed materials will be properly packaged in 6ml double bags and will be appropriately disposed of in a discreet fashion.

Mold Busters' trained remediation professionals are recommended to wear dust impermeable gloves, half-face air purifying respirator (P-100), full body dust-impervious coveralls, and boot covers or separate work boots.

Price includes labor, material, travel, disposal, and equipment fees.
Any additional items and areas that require removal or treatment are subject to revision and discussion with the client.

- In the case additional layers of drywall and flooring are found during the remediation project, a scope increase will be presented to the client for consideration

-- 3 - Cleaning and Disinfection
Thorough HEPA vacuuming is conducted throughout all surfaces in the affected bathroom area in order to remove mold spores, particulates, and dust.

All remaining surfaces (studs, beams, walls, floors, etc.) in the bathroom will be disinfected, by concentrated fogging, using an approved fungicide.

Additional vacuuming or HEPA air scrubbing may occur upon completion of the fogging process, along with a general cleaning of all areas traveled by Mold Busters personnel.

Mold Busters applies an advanced, two-stage mold remediation protocol, initiating with high-precision stain removal techniques to revitalize the aesthetics of affected surfaces. This is seamlessly followed by the strategic application of our proprietary fungicides, meticulously designed to eliminate mold spores, thereby ensuring your space is restored to its pristine condition and safeguarded against future contamination.

-- 4 - Post-Removal Clearance (Swab)
Post-remediation verification is conducted to ensure that the environment has been successfully remediated.

The final clearance inspection includes a visual inspection and an instant swab analysis.

This will be performed by the Project Supervisor upon completion of the remediation process.

-- Project Clearance Report
A written report following the remediation process, describing the outcome of the remediation work, any potential source issues, clearance grades, etc.

Additional recommendations will be made in this report to assist in preventing future fungal contamination.

-- Notes
"

Estimated Project Time: 4 hours

Please note that this is only an estimated timeframe provided for your reference. We do not charge by the hour—our pricing is all-inclusive, covering time, travel, labour, materials, and disposal for the full scope of work.",

Subtotal	$1,495.00
Taxes	$194.35
Total	$1,689.35 CAD

Terms (as shown to the client)

Why clients choose Mold Busters:

• Strong reputation with top-rated client reviews
• Competitive and transparent pricing
• Work completed according to detailed scope — no shortcuts
• If anything is not completed as outlined, we will return and address it at no additional cost

Please note that the project time is only an estimated timeframe provided for your reference. We do not charge by the hour—our pricing is all-inclusive, covering time, travel, labour, materials, and disposal for the full scope of work.

By accepting this estimate, you agree to our Terms & Conditions:
https://iaq.is/terms-conditions

Estimate pricing includes all time, travel, labor, disposal, and/or materials costs.
Unless otherwise indicated, vacancy is required for the duration of the active project hours, and reconstruction services are not provided.

A 40% booking deposit is required upon acceptance of the estimate to reserve your requested date(s) and proceed with scheduling.

Due to mold being a living organism, mold removal estimates are only valid for 60 days from the date of inspection. Acceptance of a mold removal estimate after 60 days may be subject to a re-assessment prior to proceeding.
This does not apply to asbestos or inorganic-related estimates.

Cancellation & Refund Terms:
- Cancel within 20 to 11 days before the start date: No fee.
- Cancel 10 to 3 days prior: 10% of invoice retained.
- Cancel within 48 hrs of start date: 40% of invoice retained.

Administrative fees apply.

GST/HST: 812780229RT0001
QST: 1221549895TQ0001
RBQ# 5726-4947-01