Mold Busters - Estimate MP291

Rebuilt from FreshBooks data for this dataset. Client name and email removed; wording of the items is unchanged.

Estimate number	MP291
Created	2026-10-07
Status in FreshBooks	viewed
Client	[removed]
Property	25 Bannock Crescent, Kanata, ON, K2K 2P8
Total	$4181.00 CAD (taxes included)

Notes

Estimated Project Time: 1 day

Items

Item	Amount	Tax
Solution Center Agent: Danica	$0.00	-
Inspector: Luka	$0.00	-
Topical & Abrasive Mold Treatment	$3,700.00	HST 13%: $481.00
Mold Clearance Guarantee with Certificate	$0.00	-

Inspector: Luka

The inspector who prepared this estimate is:
Luka Markovic, MSC ME, CMI

Got questions? Contact Luka by phone at: 343-600-3453, or by email: luka@bustmold.com

Topical & Abrasive Mold Treatment

- Containment Process

To protect the rest of the property, the affected areas will be fully contained using durable polyethylene barriers and zipper door access points.
When conditions allow, negative air pressure will be used to help prevent the spread of dust, mold spores, and other airborne particles.
If not feasible, an equivalent containment method will be applied.

Affected area(s):
• Two washrooms and the attic

We kindly ask that all personal belongings be removed from the affected areas prior to the start of work.

Any large items that cannot be moved will be carefully covered and protected to minimize exposure to dust and debris during the remediation process.

- Topical Treatment Process

Once the affected materials are exposed, our team will remove mold from structural surfaces using a combination of specialized cleaning methods, including manual techniques and HEPA vacuuming.

We then apply a professional two-step treatment process:

Step 1: Detailed cleaning to remove staining and restore the appearance of affected surfaces
Step 2: Application of an advanced, eco-conscious fungicide designed to eliminate mold spores and help prevent future growth

Areas and materials treated may include:

- drywall ceilings
- grout
- tiles
- attic trusses and sheathing

Please note that some non-mold-related staining may remain after treatment.

All work is carried out by trained Mold Busters professionals using appropriate protective equipment and in accordance with industry standards:
- https://iaq.is/mold-removal-guidelines

Pricing includes all labor, materials, and equipment required to complete the work.

If additional affected areas are discovered during the process, any changes will be reviewed and discussed with you before proceeding.

- Disinfection Process

After the main cleaning phase, all surfaces within the contained area will be thoroughly HEPA vacuumed to remove any remaining dust, mold spores, and fine particles.

We will then apply a disinfecting treatment using a targeted fogging method with an eco-friendly solution to ensure all exposed surfaces are addressed.

As a final step:

Additional air cleaning or HEPA vacuuming may be performed if needed
All work areas, including pathways used by our team, will be cleaned before completion

- Post-Removal Clearance (Swab) x3

Post-remediation verification is conducted to ensure that the environment has been successfully remediated.

The final clearance inspection includes a visual inspection and an instant swab analysis.

This will be performed by the Project Supervisor upon completion of the remediation process.

-- Additional Notes

All work is performed by trained professionals using appropriate
protective equipment

The project includes all standard labor, materials, travel, and disposal
costs

Any changes to the scope will always be discussed and approved
before proceeding

All work is carried out by trained Mold Busters professionals using appropriate protective equipment and in accordance with industry standards:
- https://iaq.is/mold-removal-guidelines

Mold Clearance Guarantee with Certificate

A written report following the remediation process, describing the outcome of the remediation work, any potential source issues, clearance grades, etc.

Additional recommendations will be made in this report to assist in preventing future fungal contamination.

Subtotal	$3,700.00
Taxes	$481.00
Total	$4,181.00 CAD

Terms (as shown to the client)

Why clients choose Mold Busters:

• Strong reputation with top-rated client reviews
• Competitive and transparent pricing
• Work completed according to detailed scope — no shortcuts
• If anything is not completed as outlined, we will return and address it at no additional cost

Reconstruction is not included in the estimate

Please note that the project time is only an estimated timeframe provided for your reference. We do not charge by the hour—our pricing is all-inclusive, covering time, travel, labour, materials, and disposal for the full scope of work.

By accepting this estimate, you agree to our Terms & Conditions:
https://iaq.is/terms-conditions

Estimate pricing includes all time, travel, labor, disposal, and/or materials costs.
Unless otherwise indicated, vacancy is required for the duration of the active project hours, and reconstruction services are not provided.

A 40% booking deposit is required upon acceptance of the estimate to reserve your requested date(s) and proceed with scheduling.

Due to mold being a living organism, mold removal estimates are only valid for 60 days from the date of inspection. Acceptance of a mold removal estimate after 60 days may be subject to a re-assessment prior to proceeding.
This does not apply to asbestos or inorganic-related estimates.

Cancellation & Refund Terms:
- Cancel within 20 to 11 days before the start date: No fee.
- Cancel 10 to 3 days prior: 10% of invoice retained.
- Cancel within 48 hrs of start date: 40% of invoice retained.

Administrative fees apply.

GST/HST: 812780229RT0001
QST: 1221549895TQ0001
RBQ# 5726-4947-01